



**Frank Bacon Machinery Sales Co.**

**21251 Ryan Road**

**Warren, MI 48091**

**586-756-4280 [www.frankbacon.com](http://www.frankbacon.com) Email: [sales@frankbacon.com](mailto:sales@frankbacon.com)**

Stock #	DESCRIPTION
13102-01	5.5KIP (25kN) Instron 8872 Dynamic Fatigue Testing System (1) Used Instron Model 8872 Servo-Hydraulic Fatigue Testing System.
<p style="text-align: center;"><b>Instron Model 8872 SPECIFICATIONS:</b></p> <p><b>System ID Number:</b> 8872J5137 <b>Force Capacity:</b> 25kN @ 3,000 PSI <b>Number of Columns:</b> 2 <b>Distance Between Columns:</b> 18" <b>Maximum Distance Between Load Cell and Table:</b> 28" <b>Overall Dimensions (W x D x H):</b> 36" x 24" x 80"(MAX) <b>Weight:</b> 634 lbs.(Frame)</p>	
<p style="text-align: center;"><b>EQUIPPED WITH:</b></p> <ul style="list-style-type: none"><li>• Hydraulic Crosshead Lifts and Controls</li><li>• Instron 3000 PSI 25 kN, 100mm Stroke, Hydrostatic Actuator, Model A1740-3042, LVDT Area = 12.82 cm<sup>2</sup>, with Moog Servo Valve</li><li>• Instron Dynacell 25 kN Capacity Fatigue Rated Load Cell</li><li>• Instron Dynacell 1 kN Capacity Fatigue Rated Load Cell</li><li>• 18"W x 16.5"D T-Slotted Table</li><li>• Instron Fast Track 8800 Controller with Instron Console &amp; WaveMatrix Software</li><li>• Instron 3 GPM 3,000 PSI Air-Cooled Hydraulic Power Supply</li></ul>	
<p style="text-align: center;"><b>FOB Warren, MI</b> <b>Cleaned, Serviced and Cycled</b> <b>30 Day Satisfaction Guaranteed Return Privilege</b></p>	
<p>*Actual Images Before Reconditioning</p>	

**Guarantee:**

Unless otherwise specified, every machine is offered with the standard **MDNA** (*MACHINERY DEALERS NATIONAL ASSOCIATION*) Return privilege to ensure your complete satisfaction. If the machine is un-satisfactory it may be returned to our warehouse, freight prepaid and in the original condition within 30 Days of shipment for a full refund less the cost of SPECIALIZED EQUIPMENT, NEW ITEMS AND RE-CERTIFICATION COSTS, When applicable. Care is taken to provide accurate specifications. However, Critical areas should be verified by Inspection.