



**Frank Bacon Machinery Sales Co.**

**21251 Ryan Road**

**Warren, MI 48091**

**586-756-4280 [www.frankbacon.com](http://www.frankbacon.com) Email: [sales@frankbacon.com](mailto:sales@frankbacon.com)**

Stock #	DESCRIPTION
13056-00	<b>110KIP (500kN) MTS 318.50 Fatigue Load Frame</b> (1) Reconditioned 110 KIP (500 kN) Capacity MTS, Model 318.50, Two Column Material Fatigue Testing Load Frame.
	<p style="text-align: center;"><b>MTS Model 318.50 SPECIFICATIONS:</b></p> <p>Model Number / Serial Number: 318.50/1292471 Load Frame Capacity (KIP): 110 (500 kN) Number Of Columns: (2) 4" Diameter Distance Between Columns: 30" Test Specimen Max. Length: 83" Table Size (W x D): 25" x 12" Approximate Overall Dimensions (W x D x H): 47" x 32" x 141" Approximate Weight (Lbs): 4,200</p>
	<p style="text-align: center;"><b>EQUIPPED WITH:</b></p> <ul style="list-style-type: none"><li>• MTS Hydraulic Lifts, Hydraulic Locks with Built-in Controls</li><li>• MTS 110KIP Actuator, Model 318.50, Assembly 484784-11 Rev A, A= 38.48 in<sup>2</sup> , 6" Stroke LVDT, S/N 1085964</li><li>• (2) MTS Piston Accumulators</li><li>• MTS MOOG 15 GPM Servo Valve Model 252.25G-04</li><li>• MTS Model 298.12 Hydraulic Service Manifold with MTS Piston Accumulators and On/Off Solenoid Valve</li><li>• MTS 110 KIP (500 kN) Fatigue Rated Load Cell, Model 661.23F-01, S/N 1148895</li></ul>
	<p style="text-align: center;"><b>FOB Warren, MI Cleaned, Serviced &amp; Cycled 90 Day Parts and Labor Warranty 30 Day Satisfaction Guarantee Return Privilege</b></p> <p>*Actual Image</p>

**Guarantee:**

Unless otherwise specified, every machine is offered with the standard **MDNA** (*MACHINERY DEALERS NATIONAL ASSOCIATION*) Return privilege to ensure your complete satisfaction. If the machine is un-satisfactory it may be returned to our warehouse, freight prepaid and in the original condition within 30 Days of shipment for a full refund less the cost of SPECIALIZED EQUIPMENT, NEW ITEMS AND RE-CERTIFICATION COSTS, When applicable. Care is taken to provide accurate specifications. However, Critical areas should be verified by Inspection.